

## **Underground Flow Equalization System Project**

Planning Commission Study Session August 27, 2019



### **Agenda**

- Report back from Planning Commission Meeting of April 9th
  - —Background
  - —Outreach Activities
- Construction impacts and monitoring
- Q&A session



May 21, 2019 Community UFES Meeting







Sanitary Sewer Overflow (SSO) at Saratoga Dr & Delaware St

### Why Is the UFES Project Needed?






- Meet Cease & Desist Order requiring prevention of sanitary sewer overflow (SSOs) and local beach closures
- Provide system capacity and optimize collection system performance during storms
- Improve safety and reliability of the system and reduce discharges of raw sewage in San Mateo and the Bay



### **Existing Storage System on Delaware St**

Temporary baker tanks








### **Summary - UFES Public Outreach Activities**

- Over 50 Community engagements since 2016
- Planning Commission Meeting April 9, 2019 DEIR, SUP & SPAR
- Recent Community Meeting on May 21, 2019 at Event Center (over 90 attendees)
- Key Commissioners & Community Concerns Areas:
  - Construction Approach & Visual Impacts
  - Piling & Shoring Method & Duration
  - Street Closures and Pedestrians and Bike Accessibility & Continued Usage
  - Noise, Dust, Vibrations, Settlement, and Traffic Management





### **Project Location & Features**



## Final UFES Site







### **UFES Site – Saratoga Drive – Before**






### **UFES Site – Event Center Entrance – Before**












### **UFES Project Phases & Construction Schedule**



#### **Construction Hours**

- Allowable construction hours are Monday to Friday, 7 am 7 pm
- Typical construction day is expected to be 8-10 hours
- Construction work is not planned for weekends or outside hours of 7 am 7 pm
  - Exceptions may be needed, but only with City approval (e.g. concrete pour)





### **Minimizing UFES Construction Impacts**

- Noise
- Dust
- Settlement
- Vibration
- Traffic
- Pipeline Construction





#### **Addressing Noise Concerns**


- Eliminated Sheet Piling shoring (not using method used at CalTrain project)
  - -Evaluated and selected three shoring alternatives with lower noise levels
- Eliminated Driven Piles for foundations
  - -Evaluated and selected drilled micropiles for foundation
- Providing noise monitoring during construction





## **Shoring Installation**

**Duration:** 4 months







### **Shoring System Evaluation Process**

- We evaluated 6 different typical shoring methods
- What factors did we use?
  - —Technical feasibility does it work for this site?
  - —Duration of installation
  - —Dewatering requirements
  - -Noise
  - —Vibration
  - —Cost






### **Technically Feasible / Selected Shoring Systems**



**Slurry Walls** 





**Deep Cement Soil Mixing** 





**Secant Pile Walls** 



### Foundation Pile Installation

**Duration:** 2 months









# Drilled Micropiles

Selected Foundation Pile Method






### **UFES Facility**













## **Drilled Micropile Installation**







## **Drilled Micropile Installation**




Section Showing Anticipated Sound Levels From Micropiling Activities – Bay Meadows





## Monitoring -Noise







Proposed Stationary Noise Monitor





### **Addressing Dust Concerns**


- Specifying compliance with Bay Area Air Quality Management District
- Using Best Management Practices is required during earth moving
- Visual observations and hand-held dust monitoring during construction





## Site Preparation

**Duration:** 3 months







#### **Excavation**

**Duration:** 3 months







### **Typical Dust Control**

#### **Construction Areas**








- Wet Sweeping on surrounding streets
- Covered trucks
- Site watering
- Fence screening
- Tire cleaning/rumble pads
- Speed limits on unpaved surfaces
- Reduced idling times
- Properly maintained equipment





## Monitoring – Dust











### **Addressing Settlement Concerns**

- Existing Groundwater Monitoring Sites since 2017 – groundwater fluctuates
- Specifying shoring and dewatering to limit settlement
- Different approach from the Concar project's dewatering methods
- Additional groundwater monitoring during construction
- Home inspections before, during and after construction










### **Additional Groundwater Monitoring - UFES Site**







### **UFES Dewatering – Fiesta Gardens Proximity**





Controlling Groundwater - Fiesta Gardens




### Other Dewatering Method – Not Feasible


NOT THE METHOD FOR THIS PROJECT

-Not technically feasible

Cone of Influence can extend beyond site limits













## **Additional Groundwater Monitoring - UFES Site**







# Construction Monitoring – Property Inspections

Preconstruction Inspection





## **Addressing Vibration Concerns**

- Collect background vibration data (traffic, nearby construction, etc.)
   prior to construction
- Fence line monitoring between the site and Fiesta Gardens and Bay Meadows
- Establish maximum vibration limits





## **Vibration Monitors at UFES Site**









### **Addressing Traffic Concerns**

- Coordinate traffic review with other projects
- Updated EIR with new traffic counts
- New Event Center easement in progress significantly reduce Saratoga impacts
- Staggered conveyance construction to limit street closures
- Provide continuous safe pedestrian and bicycle routing





# Construction Traffic Routes Normal Conditions

- City Designated Truck/Haul Routes
- Proposed Primary Project Haul Route
- Proposed Secondary Project Haul Route


UFES Holding Tank Site





#### **Concrete**

**Duration:** 9 months







# Diversion System Alignments & Locations

#### Diversion Structure

—South of Saratoga and Delaware Intersection

#### Diversion Sewer

—New 36-inch diameter, 15 to 22 feet deep

#### Force Main

—18-inch sewer pipe (lining existing pipe)





### **Addressing Pipeline Construction Concerns Along Streets**

- Trenchless methods to reduce traffic impacts
  - —Borel Creek force main crossing
  - —Lining of existing sewer for force main
- Staggered pipeline construction limits traffic impacts in the area
  - —Delaware and Saratoga
- Provide safe pedestrian and cyclist access throughout construction period





# **Diversion Sewer Open Trench Construction**










#### Force Main Trenchless Construction

Borel Creek Culvert
 Undercrossing at Delaware
 Horizontal directional drilling
 of New 18" Force Main

Saratoga Force Main
 Cured in Place Pipe Lining of Existing 18" Pipe










CLEANWATER PROGRAM

#### **Diversion Structure Construction**

- Excavation in intersection of Delaware and Saratoga
- Temporary shoring
- Traffic control around excavation
- Duration: 3 months







## **Communicating with the Public**

- Construction hotline live access to contractor 24/7
- City's existing program website
  - Construction updates will be provided on a regular basis
- Updates posted at the site
- Email newsletter
- Other forms of communication (e.g., social media)





# Site Finishing: Last Step

**Duration:** 8 months







### **UFES Operations and Maintenance**

- Facility used during storms up to 20 times per year on average
- Routine maintenance quarterly
- Odor control system operates continuously
- Holding structure cleaned with the tipping buckets and emptied after each use
- Inspected by City after each event





#### **Odor Control**








Carbon Odor Scrubber

- Highly efficient technology: carbon odor scrubbers
- Large pore surface area adsorbs large mass of odors
- 1 teaspoon has surface area of a football field!





# **CEQA/EIR Updates**

- Extended Public Comment Period to May 31, 2019
  - -87 day comment period (45 days required by CEQA)
- Currently responding to over 470 comments
- Final EIR will be released September 6, 2019 for public comment prior to Planning Commission Meeting





#### **Next Steps**

- Planning Commission Recommendation (Final EIR/Special Use Permit) Meeting:
   September 24, 2019
- City Council Final EIR/Special Use Permit Hearing on October 21, 2019
- Anticipated Construction Start: Spring 2020





#### **Summary**

- Addressed key community concerns for construction impacts & monitoring
- Selected low-impact construction methods for piles and shoring
- Developed monitoring approach for pre, during, and post-construction activities
- Active construction mitigation (noise, vibration, dust)
- Coordinated approach to traffic management to reduce impacts







### Please share methods to effectively communicate

#### **Sign Up for Email Updates**

info@cleanwaterprogramsanmateo.org

#### **Visit the UFES Project Website**

www.CleanWaterProgramSanMateo.org/UFES

#### **Call the Clean Water Program**

650-727-6870

#### **Follow the City's Social Media**









